



Attachment 1

Notes - City Hall Heat Pump Replacement Project

SCOPE OF WORK:

- Units to be replaced are ceiling mounted on all three floors and original to building (1992).
- Current units - Carrier 50QXH. Several replaced with Carrier 50PCH units in past.
- New units to meet or exceed Carrier 50PCH specs with MERV 13 filters as listed in drawings.
- Excluded units: 1-1, 1-2, 1-8, 1-10, 2-1, 2-2
- To include modification and/or rearrangement of the following units providing for better filter panel access: 1-6, 1-9, 2-3, 2-6, 2-8
- Selected Contractor to submit shop drawings for review by project engineering partner, JDR Engineering.
- Contractor to provide electronic copies of O & M manuals for new units.
- Selected Contractor to submit background checks and fingerprinting to PD for approval. Badges will be provided for access to PD areas upon install date.